


MISSISSIPPI ASBESTOS DEMOLITION/RENOVATION NOTIFICATION FORM

Mail notification to: MDEQ Asbestos and Lead Branch, 515 E. Amite Street, Jackson, MS 39201

MDEQ Use Only: ☒ Email ☐ Mail ☐ Hand Delivery		Postmark (mail only) 04/17/2025 EM	Date Received 05/01/2025	AI Number 8997
I. Type of Notification (O=Original R=Revised C=Canceled A= Annual) Original				
II. TYPE OF OPERATION (D=Demo O= Ordered Demo R=Renovation E=Emer. Renovation) Demo (RELOCATION) (ACM Removal ONLY)				
III. FACILITY DESCRIPTION (Include building name, number and floor or room number) Two Residential Houses next to our Ecru Facility				
Bldg. Name: Two Residential Houses				
Address 782 QT Todd Road and 635 HWY 346				
City: Ecru	State: MS	Zip: 38841	County: Pontotoc	
Site Location: Northwest corner of Ashley Furniture Ecru Facility see report		Tel: 608.323.1871		
Building Size Combined they are ~4,000 sqft	# of Floors: 1	Age in Years: ???		
Present Use: Vacant	Prior Use: Residential			
IV. FACILITY INFORMATION (Identify owner, asbestos removal contractor, and other operator)				
OWNER NAME: Ashley Furniture Industries, LLC				
Address: One Ashley Way				
City: Arcadia	State: WI	Zip: 54612		
Contact: Andy Meinerz	Tel: 608.323.1871			
ASBESTOS REMOVAL CONTRACTOR: EAC Environmental - Edward Clay				
Address: 4546 Cal-Steens Rd				
City: Caledonia	State: MS	Zip: 39740		
Contact: Edward Clay	Tel: 662.386.6386			
Certification Number: ABC-00005192		Expiration Date: 11/4/2025		
OTHER OPERATOR:				
Address:				
City:	State:	Zip:		
Contact:	Tel:			
V. WAS SITE INSPECTED TO DETERMINE PRESENCE OF ASBESTOS? (Yes/No): Yes				
WAS ASBESTOS PRESENT? (Yes/No): Yes see reports		Inspection Date: 4/22/2025		
Inspector: Jacob Webb	Certification Number: ABI-00012653	Expiration Date: 1/3/2026		
VI. SUSPECT MATERIALS SAMPLED AND PROCEDURES USED TO DETECT THE PRESENCE OF ASBESTOS MATERIAL:				
Approximately 35 SF of vinyl flooring in bathroom - Non Friable				
Approximately 65 SF of vinyl flooring in laundry room - Non Friable				
See asbestos reports attached				
VII. QUANTITY OF RACM TO BE REMOVED: See reports				
Pipes (LN FT):	Surface Area (SQ FT): ~100sqft	Volume of Facility Components (CU FT):		
VIII. QUANTITY OF NONFRIABLE ASBESTOS NOT REMOVED:				
Category I: 0	Category II: 0			
IX. SCHEDULED DATES ASBESTOS REMOVAL (MM/DD/YY) Start: 5/3/2025		Complete: 5/3/2025		
X. SCHEDULED DATES DEMO/RENOVATION (MM/DD/YY) Start: 5/7/2025		Complete: 5/10/2025		

XI. DESCRIPTION OF PLANNED DEMOLITION OR RENOVATION WORK, AND METHOD(S) TO BE USED:		
Houses will be relocated.		
XII. DESCRIPTION OF WORK PRACTICES AND ENGINEERING CONTROLS TO BE USED TO PREVENT EMISSIONS OF ASBESTOS AT THE DEMOLITION OR RENOVATION SITE:		
Asbestos will be removed prior to relocation		
XIII. WASTE TRANSPORTER #1		
Name: EAC Enviromental (same info as above)		
Address:		
City:	State:	Zip:
Contact Person:	Tel:	
WASTE TRANSPORTER #2		
Name: Waste Pro		
Address: 1600 S 12th Ave		
City: Columbus	State: MS	Zip: 39701
Contact Person:	Tel:	
XIV. WASTE DISPOSAL SITE		
Name: ROBO Landfill		
Address: 6447 Wahalak Rd		
City: Scooba	State: MS	Zip: 39358
Contact Person:	Tel:	
XV. IF DEMOLITION ORDERED BY A GOVERNMENT AGENCY, PLEASE IDENTIFY THE AGENCY BELOW:		
Name: N/A	Title:	
Authority:		
Date of Order (MM/DD/YY):	Date Ordered to Begin (MM/DD/YY):	
XVI. FOR EMERGENCY RENOVATIONS: N/A		
Date and Hour of Emergency (MM/DD/YY):		
Description of the sudden unexpected event:		
Explanation of how the event caused unsafe conditions or would cause equipment damage or an unreasonable financial burden:		
XVII. DESCRIPTION OF PROCEDURES TO BE FOLLOWED IN THE EVENT THAT UNEXPECTED ASBESTOS IS FOUND OR PREVIOUSLY NONFRIABLE ASTESTOS MATERIAL BECOMES CRUMBLED, PULVERIZED, OR REDUCED TO POWDER:		
EAC will consult with owners to address. Likely will remove any additional ACM found.		
XVIII. I CERTIFY THAT AN INDIVIDUAL TRAINED IN THE PROVISIONS OF THIS REGULATION (40 CFR PART 61, SUBPART M) WILL BE ONSITE DURING THE DEMOLITION OR RENOVATION, AND EVIDENCE THAT THE REQUIRED TRAINING HAS BEEN ACCOMPLISHED BY THIS PERSON WILL BE AVAILABLE FOR INSPECTION DURING NORMAL BUSINESS HOURS.		
Edward Clay Type or Print Name	 (Signature of Owner/Operator)	5/1/2025 (Date)
XIX. I CERTIFY THAT THE ABOVE INFORMATION IS CORRECT:		
Andy Melnerz Type or Print Name	 (Signature of Owner/Operator)	5/1/2025 (Date)



Cobb Environmental & Technical Services, Inc.

Construction • Fueling Systems • Environmental

April 28, 2025

Ashley Furniture
ATTN: Andy Meinerz
1 Ashley Way
Arcadia, WI 54612

**RE: Asbestos Survey for Demolition Purposes
Property Located at 781 Q.T. Todd Drive
Pontotoc, MS 38863**

Dear Mr. Meinerz,

Cobb Environmental & Technical Services, Inc. (CETS) is pleased to submit the following report of our findings at the referenced site. The asbestos survey and sampling were performed by Mr. Jake Webb. Laboratory analysis was completed by the National Econ Corporation Laboratory in Memphis, TN.

A copy of Mr. Webb's certification is presented as **Appendix A** to this report.

Introduction

CETS was requested by Mr. Andy Meinerz, on Thursday, April 17, 2025, to conduct an asbestos survey for demolition purposes of the referenced facilities. CETS inspector, Jake Webb, visited the site on, April 22, 2025, to collect samples of the residential property located at 781 Q.T. Todd Drive in Pontotoc, MS. A brief description of the sampled areas is included in the attached tabulation of analytical results. Representative samples were collected from homogeneous areas and sent via overnight courier to the laboratory.

Summary of Findings

CETS collected 33 samples throughout the residential building and collected four (4) samples throughout the shed/utility building at the rear of the property at 781 Q.T. Todd Drive. One (1) of the samples was found to be containing asbestos via laboratory analysis by polarized light microscopy. The following tables are a summary of the building materials sampled and laboratory findings. A copy of the supporting laboratory report is presented as Appendix B. **Appendix C** contains a copy of the MDEQ Demolition / Renovation form for your convenience.

Report On Asbestos Inspection Of
Residential Property and Shed
781 Q.T. Todd Drive
Pontotoc, MS 38863

Sample I.D.	Sample Description / Location	Analytical Results (%)	Type, notes
		PLM	
1	Roof; Friable, Composite, Black Shingles	ND	Misc
2	Roof; Friable, Grab, Black Roof Underlay	ND	Misc
3	Exterior Brick, Friable, Grab, Gray Grout	ND	Misc
4	Interior Brick, Friable, Grab, Gray Grout	ND	Misc
5	Throughout Except One Bedroom; Composite, Friable, Brown Carpet	ND	Misc
6	Living Room; Composite, Friable Yellow & Pink Carpet Padding	ND	Misc
7	Living Room; Composite, Friable Blue Wall Paper with some Drywall Spackling	ND	Misc
8	Living Room; Grab, Friable, White Drywall Spackling	ND	Misc
9	Living Room; Composite, Friable, White & Brown Drywall	ND	Misc
10	Living Room; Composite, Friable, White & Brown Popcorn Ceiling Texture with some Drywall Material	ND	Misc
11	Kitchen; Grab, Friable, White & Yellow Ceiling Texture	ND	Misc
12	Kitchen; Nonfriable, Composite, White & Brown Wall Paper with Glue	ND	Misc
13	Kitchen; Composite, Nonfriable, White & Brown Counter Facing with Glue	ND	Misc
14	Laundry Room; Grab, Nonfriable, Dark Yellow Vinyl Flooring	30	Misc
15	Dining Room; Composite, NonFriable, Light Colored and Brown Faux Wood Facing	ND	Misc
16	Dining Room; Composite, NonFriable, 2nd Layer Brown Faux Wood Facing	ND	Misc
17	"Mike's Room; Composite, Friable, Green Carpet with Glue	ND	Misc
18	"Mike's Room; Composite, Friable, Dark Tan Carpet Padding with Pink Adhesive	ND	Misc
19	Hallway; Grab, Friable, Pink & Brown Carpet Padding	ND	Misc
20	Bathroom; Grab, Friable, Gray & White Floor Tile Grout	ND	Misc
21	Bathroom; Friable, Composite, Gray Floor Grout with Glue & Tan Paperlike Substance	ND	Misc
22	Bathroom/Hallway Transition Cover; Friable, Composite, Dark Tan & White Adhesive Compounds	ND	Misc
23	Bathroom, Composite, Friable, Yellow & Light Pink Wall Paper with Glue	ND	Misc
24	Bathroom; Friable, Grab, Sink Counter Caulk	ND	Misc
25	Bathroom Shower; Friable, Composite, White & Gray Tile Caulking	ND	Misc
26	Utility Closet; Friable, Composite, Yellow & Silver HVAC Insulation	ND	Misc
27	Utility Closet; Friable, Composite, Gray and Black Foam Pipe Insulation	ND	Misc
28	Utility Closet; Grab, Friable, Grab, Black Floor Lining	ND	Misc
29	Rear Bathroom; Friable, Composite, Tan & Brown Flooring with Glue	ND	Misc
30	Rear Bathroom; Friable, Composite, White & Brown Wall Facing	ND	Misc

31	Rear Bathroom; Nonfriable, Grab, White Silicon-like Counter Caulk	ND	Misc
32	Attic; Friable, Grab, Pink & Yellow Insulation	ND	Misc
33	Attic; Friable, Composite, Silver & Pink HVAC Insulation	ND	Misc
Shed Samples			
34	Exterior; White and Brown Wall Siding	ND	Misc
35	Bathroom, Friable, Composite, White Wallpaper with Glue	ND	Misc
36	Attic; Composite, Friable, Pink and Yellow Insulation	ND	Misc
37	Attic; Composite, Friable, Black and Brown Interior Wall Siding	ND	Misc
NOTES, ABBREVIATIONS			
ND – None detected		TSI – Thermal System Insulation	
Misc. – Miscellaneous, non-TSI, non-coating material		PLM – Polarized Light Microscopy (lab method)	
<1 – Asbestos detected, less than regulated concentration			

If you have any further questions or comments, please do not hesitate to contact the undersigned.

Very Truly Yours,
Cobb Environmental and Technical Services, Inc.



Jake Webb
Inspector #ABI-00012653

Appendix A Certifications

State of Mississippi

*Department of Environmental Quality
Office of Pollution Control*

Certificate of Licensure

In accordance with the Asbestos Abatement Accreditation and Certification Act,
Enacted as 1989 Mississippi Law, Chapter 505

Be it known that

Jacob R Webb

Having submitted acceptable evidence of qualifications and
training and other appropriate information, is hereby granted this

***Asbestos Inspector
Certification***



Chief, Asbestos & Lead Branch

*Certificate No.: ABI-00012653
Expiration Date: Jan 3rd, 2026
Training Expires on Jan 3rd, 2026*

85923 LIC20250001

CERTIFICATE OF COMPLETION

Jacob R Webb

XXX-AL-3099

P.O. Box 1602

Tupelo, MS 38802

has attended and satisfactorily completed course exam with a passing score of 70% or better

Asbestos Inspection & Assessment Refresher – English

EPA/AHERA Approved Under TSCA Title II



rgnp dist.

475 Norris Dean Road
Mantee, Mississippi 39751
1-662-263-3860
rgnpdist@gmail.com

Location of Training:

Forest Community Center
111 County Road 89
Ethelsville, AL 35461

RGNPAIAR0032-4

CERTIFICATE NUMBER

January 3, 2026

EXPIRATION DATE



Accredited Training Provider

COURSE INSTRUCTOR

January 3, 2025

EXAMINATION DATE

COURSE INSTRUCTOR

NORICE DEAN NASH – PRINCIPAL INSTRUCTOR /
COURSE TRAINING MANAGER

January 3, 2025

COURSE DATE(S)

Appendix B

Laboratory Report

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	1	2	3
Asbestos Minerals	Black Bituminous	Black Bituminous	Gray Granular
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers			
Fibrous Glass	20		
Perlite			
Tar	40	30	
Synthetics Fiber			
Filler / Binder		60	40
Granular Minerals	40		60
Other		10	
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	4	5	6
Asbestos Minerals	Gray Granular	Brown Fibrous	Pink Synthetic
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers			
Fibrous Glass			
Other		10	
Synthetics			100
Synthetics Fiber		70	
Filler / Binder	60	20	
Granular Minerals	40		
Glue			
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	7	8	9
	Blue-Tan Granular	White Powdery	Tan Granular
Asbestos Minerals			
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers		2	20
Fibrous Glass			
Paint	5		
Synthetics			
Micas	15	15	
Filler / Binder	40	50	30
Granular Minerals	40	33	50
Glue			
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Bulk Sample Test Report

Sample Number	10	11	12
Asbestos Minerals	Tan Granular	Cream Granular	Cream Vinyl
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers			
Vinyl			70
Paint	5	30	
Micas	10		
Synthetics Fiber			
Filler / Binder	35	50	30
Granular Minerals	50	20	
Glue			
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Nettla Cooper

Sample Number	13	14	15
Asbestos Minerals	Tan Consolidated	Yellow Layered	Brown Fibrous
Chrysotile		30	
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers		20	50
Fibrous Glass			
Perlite			
Vinyl		30	
Synthetics Fiber			15
Filler / Binder	40	20	35
Granular Minerals	55		
Glue	5		
Comments:	No Asbestos Detected	30% Chrysotile Asbestos	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS
Lab I.D. Number: 202504224
Analyst: Netta Cooper

Sample Number	16	17	18
Asbestos Minerals	Brown Fibrous	Green Synthetics	Tan Synthetics
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers			
Other			2
Synthetic Foam			98
Wood	98		
Synthetics Fiber		98	
Filler / Binder	2		
Granular Minerals			
Glue		2	
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	19	20	21
<u>Asbestos Minerals</u>	Tan Synthetics	Tan Granular	Tan Granular
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
<u>Non-Asbestos</u>			
Cellulose / Wood Fibers			
Fibrous Glass			
Other	5		30
Synthetic Foam	95		
Synthetics Fiber			
Filler / Binder		40	40
Granular Minerals		60	20
Glue			
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	22	23	24
	Tan Granular	Tan Fibrous	Cream Granular
Asbestos Minerals			
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers		40	
Fibrous Glass			
Other		25	
Synthetics			
Synthetics Fiber			
Filler / Binder	25	10	45
Granular Minerals	75	25	55
Glue			
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	25	26	27
<u>Asbestos Minerals</u>	White Granular	Yellow Fibrous	Black Synthetics
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
<u>Non-Asbestos</u>			
Cellulose / Wood Fibers		5	
Fibrous Glass		90	
Perlite			
Synthetics			100
Synthetics Fiber			
Filler / Binder	30	5	
Granular Minerals	45		
Other	25		
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	28	29	30
Asbestos Minerals	Black Layered	Brown Consolidated	Brown Fibrous
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
Non-Asbestos			
Cellulose / Wood Fibers		30	90
Fibrous Glass			
Perlite			
Vinyl		30	
Synthetics Fiber			
Filler / Binder	40	40	10
Granular Minerals			
Other	60		
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	31	32	33
<u>Asbestos Minerals</u>	White Synthetics	Pink Fibrous	Pink Fibrous
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
<u>Non-Asbestos</u>			
Cellulose / Wood Fibers			3
Fibrous Glass		98	90
Perlite			
Synthetics	90		
Synthetics Fiber			
Filler / Binder	10	2	5
Granular Minerals			
Foil			2
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

National Econ Corporation
4646 Poplar Avenue, Suite 206 - Memphis, Tennessee 38117
(901) 208-2832

Bulk Sample Test Report

Date Analyzed: April 24, 2025 Lab I.D. Number: 202504224
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS Analyst: Netta Cooper

Sample Number	34	35	36
<u>Asbestos Minerals</u>	Brown Fibrous	White Fibrous	Pink Fibrous
Chrysotile			
Anthophyllite			
Crocidolite			
Actinolite/ Tremolite			
<u>Non-Asbestos</u>			
Cellulose / Wood Fibers	90	70	
Fibrous Glass			100
Perlite			
Synthetics		30	
Synthetics Fiber			
Filler / Binder	10		
Granular Minerals			
Glue			
Comments:	No Asbestos Detected	No Asbestos Detected	No Asbestos Detected

Analyst: *Marvinella Cooper*

Approved Signatory: *Marvinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.

Bulk Sample Test Report

Date Analyzed: April 24, 2025
Client / Project Name: CETS / 781 Q.T. Todd Dr., Pontotoc, MS
Lab I.D. Number: 202504224
Analyst: Netta Cooper

Lab I.D. Number: 202504224
Analyst: Netta Cooper

[illegible]

Analyst: Marwinella Cooper

Approved Signatory: *Marwinella Cooper*

Comments: National Econ Corporation participates in the American Industrial Hygiene Association (AIHA) - Bulk Asbestos PAT Program (BAPAT). For all obviously heterogeneous samples easily separated into sub-samples, and for layered samples, each component was analyzed separately. Disclaimer: Difficult samples such as floor tile, roofing material and samples containing < 1% asbestos, may require additional analysis by TEM or SEM if No Asbestos Detected is reported. The above test report relates only to the items tested. This test report relates only to the material analyzed. This sample was analyzed using the technique contained in 40 CFR 763, Subpart F, Appendix A (AHERA). Results from this report must not be reproduced, except in full, with the approval of National Econ Corporation.



Cobb Environmental & Technical Services, Inc.

Cobb Environmental and Technical Services, Inc
871 South Green street
Tupelo, MS 38804

Phone 662-841-0995

FAX 662-841-0810

Chain of Custody
ASBESTOS

Page:

1 of 2

Project # E-4552-MS Date: Tuesday, April 22, 2025
Site Name: Residential Buildings
Location: 781 Q.T. Todd Dr., Pontotoc, MS 38863

Sample Number	Sample Description	Date Collected	Required Analysis	Lab ID
1	Roof; Friable, Composite, Black Shingles	4/22/2025	PLM	
2	Roof; Friable, Grab, Black Roof Underlay	4/22/2025	PLM	
3	Exterior Brick; Friable, Grab, Gray Grout	4/22/2025	PLM	
4	Interior Brick; Friable, Grab, Gray Grout	4/22/2025	PLM	
5	Throughout Except One Bedroom; Composite, Friable, Brown Carpet	4/22/2025	PLM	
6	Living Room; Composite, Friable Yellow & Pink Carpet Padding	4/22/2025	PLM	
7	Living Room; Composite, Friable Blue Wall Paper with some Drywall Spackling	4/22/2025	PLM	
8	Living Room; Grab, Friable, White Drywall Spackling	4/22/2025	PLM	
9	Living Room; Composite, Friable, White & Brown Drywall	4/22/2025	PLM	
10	Living Room; Composite, Friable, White & Brown Popcorn Ceiling Texture with some Drywall Material	4/22/2025	PLM	
11	Kitchen; Grab, Friable, White & Yellow Ceiling Texture	4/22/2025	PLM	
12	Kitchen; Nonfriable, Composite, White & Brown Wall Paper with Glue	4/22/2025	PLM	
13	Kitchen; Composite, Nonfriable, White & Brown Counter Facing with Glue	4/22/2025	PLM	
14	Laundry Room; Grab, Nonfriable, Dark Yellow Vinyl Flooring	4/22/2025	PLM	
15	Dining Room; Composite, NonFriable, Light Colored and Brown Faux Wood Facing	4/22/2025	PLM	
16	Dining Room; Composite, NonFriable, 2nd Layer Brown Faux Wood Facing	4/22/2025	PLM	
17	"Mike's Room; Composite, Friable, Green Carpet with Glue	4/22/2025	PLM	
18	"Mike's Room; Composite, Friable, Dark Tan Carpet Padding with Pink Adhesive	4/22/2025	PLM	
19	Hallway; Grab, Friable, Pink & Brown Carpet Padding	4/22/2025	PLM	
20	Bathroom; Grab, Friable, Gray & White Floor Tile Grout	4/22/2025	PLM	
21	Bathroom; Friable, Composite, Gray Floor Grout with Glue & Tan Paperlike Substance	4/22/2025	PLM	
22	Bathroom/Hallway Transition Cover; Friable, Composite, Dark Tan & White Adhesive Compounds	4/22/2025	PLM	
23	Bathroom, Composite, Friable, Yellow & Light Pink Wall Paper with Glue	4/22/2025	PLM	
24	Bathroom; Friable, Grab, Sink Counter Caulk	4/22/2025	PLM	
25	Bathroom Shower; Friable, Composite, White & Gray Tile Caulking	4/22/2025	PLM	
26	Utility Closet; Friable, Composite, Yellow & Silver HVAC Insulation	4/22/2025	PLM	
27	Utility Closet; Friable, Composite, Gray and Black Foam Pipe Insulation	4/22/2025	PLM	
28	Utility Closet; Grab, Friable, Grab, Black Floor Lining	4/22/2025	PLM	
29	Rear Bathroom; Friable, Composite, Tan & Brown Flooring with Glue	4/22/2025	PLM	

Relinquished by: Jake Webb [Signature] Date, Time 4/22/2025 15:00
Received by: [Signature] Date, Time 4/24/25
Received by: _____ Date, Time _____



Cobb Environmental & Technical Services, Inc.

Cobb Environmental and Technical Services, Inc
871 South Green street
Tupelo, MS 38804

Phone 662-841-0995

FAX 662-841-0810

Chain of Custody
ASBESTOS

Page:

2 of 2

Site Name: Project # E-4552-MS Date: Tuesday, April 22, 2025
Location: Residential Buildings
781 Q.T. Todd Dr., Pontotoc, MS 38863

Sample Number	Sample Description	Date Collected	Required Analysis	Lab ID
30	Rear Bathroom; Friable, Composite, White & Brown Wall Facing	4/22/2025	PLM	
31	Rear Bathroom; Nonfriable, Grab, White Silicon-like Counter Caulk	4/22/2025	PLM	
32	Attic; Friable, Grab, Pink & Yellow Insulation	4/22/2025	PLM	
33	Attic; Friable, Composite, Silver & Pink HVAC Insulation	4/22/2025	PLM	
Shed Samples				
34	Exterior; White and Brown Wall Siding	4/22/2025	PLM	
35	Bathroom, Friable, Composite, White Wallpaper with Glue	4/22/2025	PLM	
36	Attic; Composite, Friable, Pink and Yellow Insulation	4/22/2025	PLM	
37	Attic; Composite, Friable, Black and Brown Interior Wall Siding	4/22/2025	PLM	

Relinquished by: Jake Webb Jake Webb Date, Time 4/22/2025 15:00
Received by: Neth Cooper Date, Time 4/24/25
Received by: _____ Date, Time _____

Appendix C
State Of Mississippi Renovation /
Demolition Notification Form

MISSISSIPPI ASBESTOS DEMOLITION/RENOVATION NOTIFICATION FORM

Mail notification to: MDEQ Asbestos and Lead Branch, 515 E. Amite Street, Jackson, MS 39201

MDEQ Use Only: ☐ Email ☐ Mail ☐ Hand Delivery		Postmark (mail only)	Date Received	AI Number
I. Type of Notification (O=Original R=Revised C=Canceled A= Annual):				
II. TYPE OF OPERATION (D=Demo O= Ordered Demo R=Renovation E=Emer. Renovation):				
III. FACILITY DESCRIPTION (Include building name, number and floor or room number):				
Bldg. Name:				
Address:				
City:		State:	Zip:	
Site Location:			Tel:	
Building Size:		# of Floors:	Age in Years:	
Present Use:		Prior Use:		
IV. FACILITY INFORMATION (Identify owner, asbestos removal contractor, and other operator)				
OWNER NAME:				
Address:				
City:		State:	Zip:	
Contact:			Tel:	
ASBESTOS REMOVAL CONTRACTOR:				
Address:				
City:		State:	Zip:	
Contact:			Tel:	
Certification Number:			Expiration Date:	
OTHER OPERATOR:				
Address:				
City:		State:	Zip:	
Contact:			Tel:	
V. WAS SITE INSPECTED TO DETERMINE PRESENCE OF ASBESTOS? (Yes/No):				
WAS ASBESTOS PRESENT? (Yes/No):			Inspection Date:	
Inspector:		Certification Number:	Expiration Date:	
VI. SUSPECT MATERIALS SAMPLED AND PROCEDURES USED TO DETECT THE PRESENCE OF ASBESTOS MATERIAL:				
VII. QUANTITY OF RACM TO BE REMOVED:				
Pipes (LN FT):		Surface Area (SQ FT):	Volume of Facility Components (CU FT):	
VIII. QUANTITY OF NONFRIABLE ASBESTOS NOT REMOVED:				
Category I:			Category II:	
IX. SCHEDULED DATES ASBESTOS REMOVAL (MM/DD/YY) Start:			Complete:	
X. SCHEDULED DATES DEMO/RENOVATION (MM/DD/YY) Start:			Complete:	

XI. DESCRIPTION OF PLANNED DEMOLITION OR RENOVATION WORK, AND METHOD(S) TO BE USED:		
XII. DESCRIPTION OF WORK PRACTICES AND ENGINEERING CONTROLS TO BE USED TO PREVENT EMISSIONS OF ASBESTOS AT THE DEMOLITION OR RENOVATION SITE:		
XIII. WASTE TRANSPORTER #1		
Name: _____		
Address: _____		
City: _____	State: _____	Zip: _____
Contact Person: _____	Tel: _____	
WASTE TRANSPORTER #2		
Name: _____		
Address: _____		
City: _____	State: _____	Zip: _____
Contact Person: _____	Tel: _____	
XIV. WASTE DISPOSAL SITE		
Name: _____		
Address: _____		
City: _____	State: _____	Zip: _____
Contact Person: _____	Tel: _____	
XV. IF DEMOLITION ORDERED BY A GOVERNMENT AGENCY, PLEASE IDENTIFY THE AGENCY BELOW:		
Name: _____	Title: _____	
Authority: _____		
Date of Order (MM/DD/YY): _____	Date Ordered to Begin (MM/DD/YY): _____	
XVI. FOR EMERGENCY RENOVATIONS:		
Date and Hour of Emergency (MM/DD/YY): _____		
Description of the sudden unexpected event: _____		
Explanation of how the event caused unsafe conditions or would cause equipment damage or an unreasonable financial burden: _____		
XVII. DESCRIPTION OF PROCEDURES TO BE FOLLOWED IN THE EVENT THAT UNEXPECTED ASBESTOS IS FOUND OR PREVIOUSLY NONFRIABLE ASBESTOS MATERIAL BECOMES CRUMBLED, PULVERIZED, OR REDUCED TO POWDER:		
XVIII. I CERTIFY THAT AN INDIVIDUAL TRAINED IN THE PROVISIONS OF THIS REGULATION (40 CFR PART 61, SUBPART M) WILL BE ONSITE DURING THE DEMOLITION OR RENOVATION, AND EVIDENCE THAT THE REQUIRED TRAINING HAS BEEN ACCOMPLISHED BY THIS PERSON WILL BE AVAILABLE FOR INSPECTION DURING NORMAL BUSINESS HOURS.		
_____ Type or Print Name	_____ (Signature of Owner/Operator)	_____ (Date)
XIX. I CERTIFY THAT THE ABOVE INFORMATION IS CORRECT:		
_____ Type or Print Name	_____ (Signature of Owner/Operator)	_____ (Date)

Mississippi Department of Environmental Quality
515 E. Amite Street
Jackson, MS 39201

February 2022

Instructions for Demolition and Renovation Form:

Top of form. Please use the above address to mail or hand deliver notifications to MDEQ.

The red columns are intended for MDEQ use only.

Section I. Select from the choices provided.

Section II. Select from the choices provided.

Section III. An entry is needed for each listed item. The information for each item is a requirement of the regulations.

Section IV. Identify the responsible owner, removal contractor, and other operator (if applicable) and give complete address and contact information for each. The asbestos removal contractor must operate under a valid certification license from MDEQ and all others performing asbestos abatement activity must have the appropriate asbestos abatement certification.

Section V. Select from the choices provided and identify the asbestos material found.
Note: The determination of the presence of asbestos requires a thorough inspection of the facility subject to the demolition or renovation operation and the individual performing this inspection must have MDEQ asbestos abatement *Inspector* certification.

Section VI. Identify every material suspected/tested for asbestos and the test methodology.

Section VII. Provide the approximate amount of friable asbestos material to be removed. This includes non-friable Category I material that has become friable or Category I material that will or has been subjected sanding, grinding, cutting, or abrading. It also includes Category II non-friable material that has a high probability of becoming or has become crumbled, pulverized, or reduced to powder by the forces expected to act on the material in the course of demolition or renovation operations.

Section VIII. Use these columns only for Demolition operations where Category I and/or Category II material will be left in place. Enter for each type of material the approximate amount to not be removed in advance of the demolition operation.

Section IX. Provide the dates for both the actual start and expected completion of asbestos removal. Changes in these dates should be reported in a "Revised" notification to MDEQ.

Section X. Provide the dates for both the actual start and expected completion of the demolition and/or renovation operation or project. Changes in these dates should be reported in a "Revised" notification to MDEQ.

Section XI. Tell of what is to be undertaken and why or how. For example, the removal of asbestos material to avoid any demolition or renovation disturbance of the material.

Section XII. Use this space to identify emission control procedures to be employed to satisfy the requirements of the regulation. For example, note emission control procedures/methods to be employed or used (adequate wetting, ploy containment, negative air, waste bagging/labeling, glove bags, etc.).

Section XIII. Identify the responsible waste transporter(s) and give complete contact information for each.

Section XIV. Identify the waste disposal site to be used and give complete contact information. Asbestos waste must be deposited at a landfill waste disposal facility that is approved or permitted to receive asbestos waste. Permitted asbestos waste disposal sites in the State of Mississippi may be found on the MDEQ web site.

Section XV. Each item listed for an *Ordered Demolition* must be answered to satisfy the requirements of the regulation.

Section XVI. Each item listed for *Emergency Renovations* must be answered to satisfy the requirements of the regulations.

Section XVII. In the event of unexpected asbestos being discovered during the performance of a demolition or renovation operation, immediate steps should be taken to bring operations into compliance with the regulations. This may require operations to be halted and conditions secured, and discussions with MDEQ for the proper course of action.

Signatures. The notification should be signed (both certifications) by the owner and/or operator in control of the regulated activity, or that person's authorized representative. Please include the typed or printed name with each signature.

Submission. Project notifications should be mailed or delivered to:

MDEQ Asbestos and Lead Branch
515 E. Amite Street
Jackson, MS 39201



May 19, 2021

Dear Mr. Meinerz,

In this report, EAC Environmental Services provides the results of the Asbestos Containing Building Material Inspection conducted May 14, 2021 at the vacant house located at 447 Hwy 346, Ecru, Mississippi.

The suspect asbestos containing materials were sampled by BB Vanlandingham and sent with Chain of Custody to Crisp Analytical (CA) Labs in Baton Rouge, Louisiana by FedEx Priority Overnight. The results identified Sample 4, the tan linoleum flooring (2nd layer) in the bathroom as containing 18% Chrysotile Asbestos.

Should you have any questions concerning this report or if we may be of any further assistance, please do not hesitate to contact us.

We appreciate the opportunity to be of service to you on this project and look forward to our continued association.

Respectfully Submitted,

Barbara B. Vanlandingham



**ASBESTOS
ANALYSIS
&
CHAIN
of
CUSTODY**

CA Labs
Dedicated to
Quality

CA Labs, L.L.C.
12232 Industriplex, Suite 32
Baton Rouge, LA 70809
Phone 225-751-5632
Fax 225-751-5634



NVLAP #200772-0
TDSHS #300370
CDPHE #AL-18111
LELAP #03069

Materials Characterization - Bulk Asbestos Analysis

Laboratory Analysis Report - Polarized Light

EAC Environmental

4546 Calsteens Rd
Caledonia, MS 39740

Attn: Edward Clay

Customer Project: 447 Hwy 346 ECRU, MS Ashley Furniture

Reference #: CBR21052716

Date: 5/17/2021

Analysis and Method

Summary of polarizing light microscopy (PLM / Stereomicroscopy bulk asbestos analysis) using the methods described in 40CFR Part 763 Appendix E to Subpart E (Interim and EPA 600 / R-93 / 116 (Improved)). The sample is first viewed with the aid of stereomicroscopy. Numerous liquid slide preparations are created for analysis under the polarized microscope where identifications and quantifications are performed. Calibrated liquid refractive oils are used as liquid mounting medium. These oils are used for identification (dispersion staining). A calibrated visual estimation is reported, should any asbestiform mineral be present. Other techniques such as acid washing are used in conjunction with refractive oils for detection of smaller quantities of asbestos. All asbestos percentages are based on calibrated visual estimation traceable to NIST standards for regulated asbestos. Traceability to measurement and calibration is achieved by using known amounts and types of asbestos from standards where analyst and laboratory accuracy are measured. As little as 0.001% asbestos can be detected in favorable samples, while detection in unfavorable samples may approach the detection limit of 0.50% (well above the laboratory definition of trace).

Discussion

Vermiculite containing samples may have trace amounts of actinolite-tremolite, where not found by PLM should be analyzed using TEM methods and / or water separation techniques. Suspected actinolite/vermiculite presence will be indicated through the sample comment section of this report.

Fibrous talc containing samples may even contain a related asbestos fiber known as anthophyllite. Under certain conditions the same fiber may actually contain both talc and anthophyllite (a phenomenon called intergrowth). Again, TEM detection methods are recommended. CA Labs PLM report comments will denote suspected amounts of asbestiform anthophyllite with talc, where further analysis is recommended.

Some samples (floor tiles, surfacings, etc.) may contain fibers too small to be detectable by PLM analysis and should be analyzed by TEM bulk protocols.

A "trace asbestos" will be reported if the analyst observes far less than 1% asbestos. CA Labs defines "trace asbestos" as a few fibers detected by the analyst in several preparations and will indicate as such under these circumstances.


Quantification of <1% will actually be reported as ≤1% (allowable variance close to 1% is high). Such results are ideal for point counting, and the technique is mandatory for friable samples (NESHAP, Nov. 1990 and clarification letter 8 May 1991) under 1% percent asbestos and the "trace asbestos". **In order to make all initial PLM reports issued from CA Labs NESHAP compliant, all <1% asbestos results (except floor tiles) will be point counted at no additional charge.**

Qualifications

CA Labs is accredited by the National Voluntary Accreditation Program (NVLAP) for selected test methods for airborne fiber analysis (TEM), and for bulk asbestos fiber analysis (PLM). All analysts have a college degree in a natural science (geology, biology, or environmental science) or are recognized by a state professional board in one these disciplines. Extensive in-house training programs are used to augment education background of the analyst. The group leader of polarized light has received supplemental McCrone Research training for asbestos identification. This report is not covered by the scope of AIHA accreditation. Analysis performed at CA Labs, LLC 12232 Industriplex, Suite 32 Baton Rouge, LA 70809.

CA Labs
Dedicated to
Quality

CA Labs, L.L.C.
12232 Industriplex, Suite 32
Baton Rouge, LA 70809
Phone 225-751-5632
Fax 225-751-5634



NVLAP #200772-0
TDSHS #300370
CDPHE #AL-18111
LELAP #03069

Overview of Project Sample Material Containing Asbestos

Customer Project: 447 Hwy 346 ECRU, MS Ashley Furniture **CA Labs Project #:** CBR21052716

Sample #	Layer #	Analysts Physical Description of Subsample	Asbestos type / calibrated visual estimate percent	List of Affected Building Material Types
----------	---------	--	--	--

4	4-2	Tan Linoleum	18% Chrysotile	
---	-----	--------------	----------------	--

Tan Linoleum


Glossary of abbreviations (non-asbestos fibers and non-fibrous minerals):

ca - carbonate	pe - perlite	fg - fiberglass	pa - palygorskite (clay)
gypsum - gypsum	qu - quartz	mw - mineral wool	
bi - binder		wo - wollastinite	
or - organic		ta - talc	
ma - matrix		sy - synthetic	
mi - mica		ce - cellulose	
ve - vermiculite		br - brucite	
ot - other		ka - kaolin (clay)	

This report relates to the items tested. This report is not to be used by the customer to claim product certification, approval or endorsement by NVLAP, NIST, AIHA LAP, LLC, or any other agency of the federal government. This report may not be reproduced except in full without written permission from CA Labs. These results are submitted pursuant to CA Labs' current terms and sale, condition of sale, including the company's standard warranty and limitations of liability provisions and no responsibility or liability is assumed for the manner in which the results are used or interpreted. Unless notified in writing to return the samples covered by this report, CA Labs will store the samples for a period of ninety (90) days before discarding. A shipping or handling fee may be assessed for the return of any samples.

CA Labs
Dedicated to
Quality

CA Labs, L.L.C.
12232 Industriplex, Suite 32
Baton Rouge, LA 70809
Phone 225-751-5632
Fax 225-751-5634



NVLAP #200772-0
TDSHS #300370
CDPHE #AL-18111
LELAP #03069

Polarized Light Asbestiform Materials Characterization

Customer Info: Attn: Edward Clay

EAC Environmental

4546 Calsteens Rd
Caledonia, MS 39740

Customer Project:

447 Hwy 346 ECRU, MS
Ashley Furniture

Turnaround Time: 2 hr

CA Labs Project #:

CBR21052716

Date: 5/17/2021

Samples Received: 5/17/2021

Date Of Sampling:

Purchase Order #:

Phone # 662-386-6386

Fax # 662-356-0025

Sample #	Com ment	Layer #	Analysts Physical Description of Subsample	Homo- geneo us (Y/N)	Asbestos type / calibrated visual estimate percent	Non-asbestos fiber type / percent	Non-fibrous type / percent
1		1-1	Tan Ceiling Tile	Y	None Detected	90% ce	10% qu, ma
2		2-1	Tan Linoleum	Y	None Detected	20% ce	80% qu, ma
		2-2	Tan Mastic	Y	None Detected		100% qu, bi
3		3-1	Green Linoleum	Y	None Detected	20% ce	80% qu, ma
		3-2	Tan Mastic	Y	None Detected		100% qu, bi
4		4-1	Tan Mastic	Y	None Detected		100% qu, bi
		4-2	Tan Linoleum	Y	18% Chrysotile		82% qu, ma

Analysis Method: Interim (40CFR Part 763 Appendix E to Subpart E) / Improved (EPA-600 / R-93/116)
Preparation Method: HCL acid washing for carbonate based samples, chemical reduction for organically bound components, oil immersion for identification of asbestos types by dispersion attaining / becke line method.

ca - carbonate	mi - mica	fg - fiberglass	ce - cellulose
gypsum - gypsum	ve - vermiculite	mw - mineral wool	br - brucite
bi - binder	ot - other	wo - wollastinite	ka - kaolin (clay)
or - organic	pe - perlite	ta - talc	pa - palygorskite (clay)
ma - matrix	qu - quartz	sy - synthetic	

Approved Signatories:

David Darby
Analyst

Senior Analyst
Alicia Stretz


Laboratory Director
Chris Williams

1. Fire Damage significant fiber damage - reported percentages reflect unaltered fibers
2. Fire Damage no significant fiber damages affecting fibrous percentages
3. Actinolite in association with Vermiculite
4. Layer not analyzed - attached to previous positive layer and contamination is suspected
5. Not enough sample to analyze

6. Anthophyllite in association with Fibrous Talc
7. Contamination suspected from other building materials
8. Favorable scenario for water separation on vermiculite for possible analysis by another method
9. < 1% Result point counted positive
10. TEM analysis suggested

CA Labs
Dedicated to
Quality

CA Labs, L.L.C.
12232 Industriplex, Suite 32
Baton Rouge, LA 70809
Phone 225-751-5632
Fax 225-751-5634



NVLAP #200772-0
TDSHS #300370
CDPHE #AL-18111
LELAP #03069

Polarized Light Asbestiform Materials Characterization

Customer Info: Attn: Edward Clay
EAC Environmental
4546 Calsteens Rd
Caledonia, MS 39740

Customer Project:
447 Hwy 346 ECRU, MS
Ashley Furniture
Turnaround Time: 2 hr

CA Labs Project #:
CBR21052716

Phone # 662-386-6386
Fax # 662-356-0025

Date: 5/17/2021
Samples Received: 5/17/2021

Date Of Sampling:
Purchase Order #:

Sample #	Com ment	Layer #	Analysts Physical Description of Subsample	Homo- geneo us (Y/N)	Asbestos type / calibrated visual estimate percent	Non-asbestos fiber type / percent	Non-fibrous type / percent
4		4-3	Black Mastic	N			
5		5-1	Tan Linoleum	Y	None Detected	20% ce	80% qu, ma

Analysis Method: Interim (40CFR Part 763 Appendix E to Subpart E) / Improved (EPA-600 / R-93/116)
Preparation Method: HCL acid washing for carbonate based samples, chemical reduction for organically bound components, oil immersion for
identification of asbestos types by dispersion attaining / becke line method.

ca - carbonate	mi - mica	fg - fiberglass	ce - cellulose
gypsum - gypsum	ve - vermiculite	mw - mineral wool	br - brucite
bi - binder	ot - other	wo - wollastinite	ka - kaolin (clay)
or - organic	pe - perlite	ta - talc	pa - palygorskite (clay)
ma - matrix	qu - quartz	sy - synthetic	

Approved Signatories:

David Darby
Analyst

Senior Analyst
Alicia Stretz

Laboratory Director
Chris Williams

1. Fire Damage significant fiber damage - reported percentages reflect unaltered fibers
2. Fire Damage no significant fiber damages affecting fibrous percentages
3. Actinolite in association with Vermiculite
4. Layer not analyzed - attached to previous positive layer and contamination is suspected
5. Not enough sample to analyze

6. Anthophyllite in association with Fibrous Talc
7. Contamination suspected from other building materials
8. Favorable scenario for water separation on vermiculite for possible analysis by another method
9. < 1% Result point counted positive
10. TEM analysis suggested



C.A. Labs, LLC 12232
Industriplex Suite 32
Baton Rouge, LA 70809

Phone: 225-751-5632
Fax: 225-751-5634
Mobile: 225-993-3471

Chain of Custody

Client Name: EAC Environmental

Client Address: 4546 Cal-Steens Road
Caledonia, MS 39740

Phone number: 662-386-6386

Fax number: 662-356-0025

Contact: Edward Clay

CA Labs job # CBR 21052716

Billing Address (if different): N/A

Send Reports to: eacenvironmental@gmail.com

Project Name: 447 Hwy 396 ECRU, MS

Reports Results ASALEY FURNITURE

VIA: EMAIL ☒ FAX ☐ VERBAL ☐

Total # Samples Submitted:

5

Total # Samples to be Analyzed:

5

Material Matrix:

Air / Bulk / Water

Asbestos:

please call ahead for availability of all rush and/or after hours samples.

TEM	TA Time	PLM	TA Time	Optical / IAQ	TA Time
<i>Circle analysis and TA time</i>		<i>Circle analysis and TA time</i>		<i>Circle analysis and TA time</i>	
AHERA	4 hour	Improved	4 hour	Allergen Particle:	2 hour
EPA Level II Drinking	8 hour	Interim	8 hour	tape/bulk/swab	4 hour
Water Wipe	16 hour		16 hour	Cyclex-d cassettes Air-	8 hour
Micro-vac	24 hour	AHERA	24 hour	o-cell cassettes	16 hour
NIOSH 7402	2 days		2 days	Anderson cultures	24 hour
Chatfield Bulk	3 days	Point Count -	3 days	Bulk/swab cultures	2 days
	5 days	(NESHAPS)	5 days	Bacteria cultures	3 days
				PCM: NIOSH 7400	5-10 days

Lead:

Circle analysis and TA time

Matrix:	Paint Chips	Soil	Air	Wipes	Wastewater	TCLP
TA Time:	8 hour	1 day	2 days	3 days	5 days	6-10 days

SAMPLE #

SAMPLE LOCATION

1	CEILING	
2	HALL FLOOR	(SAME THROUGHOUT - EXCEPT BATHROOM)
3	BATHROOM	TOP LAYER
4	BATHROOM	BOTTOM LAYER
5	RIGHT SIDE BED ROOM	CLOSET
6		
7		
8		
9		
10		

Custody Information:

Samples relinquished:

BB Vandenberg 05-14-21
Signature / Date / Time

Samples received:

9:45
5-17-2021
Signature / Date / Time

Samples relinquished:

Signature / Date / Time

Samples received:

Signature / Date / Time

State of Mississippi

***Department of Environmental Quality
Office of Pollution Control***

Certificate of Licensure

In accordance with the Asbestos Abatement Accreditation and Certification Act,
Enacted as 1989 Mississippi Law, Chapter 505

Be it known that

Barbara B Vanlandingham

Having submitted acceptable evidence of qualifications and
training and other appropriate information, is hereby granted this

Asbestos Inspector

Certification



Chief, Air Division

***Certificate No.: ABI-00007369
Expiration Date: Jul 18th, 2021
Training Expires on Jul 18th, 2021***

58659 LIC20200005



ASBESTOS •Inspections •Abatement
MOLD •Inspections •Remediation
LEAD PAINT •Testing •Renovation
AIR QUALITY •Monitoring •Evaluation

Edward A. Clay

Remediation Specialist

26 Years Experience

(662)386-6386

BB Vanlandingham

(662)549-1777

FAX: 662-356-0025

Email: EACEnvironmental@gmail.com

Thank You for entrusting us with your environmental needs.

