

# MISSISSIPPI ASBESTOS DEMOLITION/RENOVATION NOTIFICATION FORM

Mail notification to: MDEQ Asbestos and Lead Branch, 515 E. Amite Street, Jackson, MS 39201

<b>MDEQ Use Only:</b> <input checked="" type="checkbox"/> Email <input type="checkbox"/> Mail <input type="checkbox"/> Hand Delivery	<b>Postmark (mail only)</b>	<b>Date Received</b> 01/28/2025	<b>AI Number</b> 1113
<b>I. Type of Notification</b> (O=Original R=Revised C=Canceled A= Annual): <b>A</b>			
<b>II. TYPE OF OPERATION</b> (D=Demo O= Ordered Demo R=Renovation E=Emer. Renovation): <b>R</b>			
<b>III. FACILITY DESCRIPTION</b> (Include building name, number and floor or room number):			
Bldg. Name: <b>Entergy Gerald Andrus Plant</b>			
Address: <b>200 MP &amp; L Road, P.O. Box 1496</b>			
City: <b>Greenville</b>		State: <b>MS</b>	Zip: <b>38702</b>
Site Location:			Tel: <b>662-379-2900</b>
Building Size: <b>N/A</b>		# of Floors: <b>11</b>	Age in Years: <b>50</b>
Present Use: <b>Electric Power Plant</b>		Prior Use: <b>Electric Power Plant</b>	
<b>IV. FACILITY INFORMATION</b> (Identify owner, asbestos removal contractor, and other operator)			
<b>OWNER NAME:</b> <b>Entergy Mississippi, LLC</b>			
Address: <b>P.O. Box 1640</b>			
City: <b>Jackson</b>		State: <b>MS</b>	Zip: <b>39215</b>
Contact: <b>Tasha Hill</b>			Tel: <b>501-258-8977</b>
<b>ASBESTOS REMOVAL CONTRACTOR:</b> <b>Apache Industrial Services, Inc.</b>			
Address: <b>250 Assay Street Suite 500</b>			
City: <b>Houston</b>		State: <b>TX</b>	Zip: <b>77044</b>
Contact: <b>Stanley E. Smith</b>			Tel: <b>409-718-5217</b>
Certification Number: <b>ABC-00012143</b>			Expiration Date: <b>2/12/2025</b>
<b>OTHER OPERATOR:</b>			
Address:			
City:		State:	Zip:
Contact:			Tel:
<b>V. WAS SITE INSPECTED TO DETERMINE PRESENCE OF ASBESTOS? (Yes/No):</b> <b>No</b>			
<b>WAS ASBESTOS PRESENT? (Yes/No):</b>			<b>Inspection Date:</b>
<b>Inspector:</b>		<b>Certification Number:</b>	<b>Expiration Date:</b>
<b>VI. SUSPECT MATERIALS SAMPLED AND PROCEDURES USED TO DETECT THE PRESENCE OF ASBESTOS MATERIAL:</b>			
Presumed asbestos. Survey will be conducted prior to abatement work. The detailed results of the survey, along with work details and detailed work methods, will be provided on a corresponding notification form at least 10 days prior to beginning work.			
<b>VII. QUANTITY OF RACM TO BE REMOVED:</b>			
Pipes (LN FT): <b>260</b>		Surface Area (SQ FT): <b>160</b>	Volume of Facility Components (CU FT): <b>35</b>
<b>VIII. QUANTITY OF NONFRIABLE ASBESTOS NOT REMOVED:</b>			
Category I: <b>NA</b>		Category II: <b>NA</b>	
<b>IX. SCHEDULED DATES ASBESTOS REMOVAL (MM/DD/YY) Start:</b> <b>1/1/2025</b>			<b>Complete:</b> <b>12/31/2025</b>
<b>X. SCHEDULED DATES DEMO/RENOVATION (MM/DD/YY) Start:</b> <b>1/1/2025</b>			<b>Complete:</b> <b>12/31/2025</b>

**XI. DESCRIPTION OF PLANNED DEMOLITION OR RENOVATION WORK, AND METHOD(S) TO BE USED:**

Presumed asbestos. Survey will be conducted prior to abatement work. The detailed results of the survey, along with work details and detailed work methods, will be provided on a corresponding notification form at least 10 days prior to beginning work.

**XII. DESCRIPTION OF WORK PRACTICES AND ENGINEERING CONTROLS TO BE USED TO PREVENT EMISSIONS OF ASBESTOS AT THE DEMOLITION OR RENOVATION SITE:**

The following procedures will be used while removing asbestos; wet method, double bagging and glove bagging.

**XIII. WASTE TRANSPORTER #1**

Name: Republic Services

Address: 1035 Old Brandon Road

City: Flowood

State: MS

Zip: 39232

Contact Person: Mike Raley

Tel: 601-613-8671

**WASTE TRANSPORTER #2 NA**

Name:

Address:

City:

State:

Zip:

Contact Person:

Tel:

**XIV. WASTE DISPOSAL SITE**

Name: BFI Little Dixie Landfill

Address: 1716 N. County Line Road

City: Jackson

State: MS

Zip: 39215

Contact Person: Mike Raley

Tel: 601-982-9488

**XV. IF DEMOLITION ORDERED BY A GOVERNMENT AGENCY, PLEASE IDENTIFY THE AGENCY BELOW:**

Name: NA

Title: NA

Authority: NA

Date of Order (MM/DD/YY): NA

Date Ordered to Begin (MM/DD/YY): NA

**XVI. FOR EMERGENCY RENOVATIONS:**

Date and Hour of Emergency (MM/DD/YY): NA

Description of the sudden unexpected event:

NA

Explanation of how the event caused unsafe conditions or would cause equipment damage or an unreasonable financial burden:

NA

**XVII. DESCRIPTION OF PROCEDURES TO BE FOLLOWED IN THE EVENT THAT UNEXPECTED ASBESTOS IS FOUND OR PREVIOUSLY NONFRIABLE ASBESTOS MATERIAL BECOMES CRUMBLED, PULVERIZED, OR REDUCED TO POWDER:**

Bring operations into compliance with the regulations and determine if project needs to be suspended with communications with MDEQ.

**XVIII. I CERTIFY THAT AN INDIVIDUAL TRAINED IN THE PROVISIONS OF THIS REGULATION (40 CFR PART 61, SUBPART M) WILL BE ONSITE DURING THE DEMOLITION OR RENOVATION, AND EVIDENCE THAT THE REQUIRED TRAINING HAS BEEN ACCOMPLISHED BY THIS PERSON WILL BE AVAILABLE FOR INSPECTION DURING NORMAL BUSINESS HOURS.**

Norberto Aguilar

Type or Print Name

*Norberto Aguilar-Carson*

(Signature of Owner/Operator)

1/30/2025

(Date)

**XIX. I CERTIFY THAT THE ABOVE INFORMATION IS CORRECT:**

Beau Griffin

Type or Print Name

*Beau Griffin*

(Signature of Owner/Operator)

1/29/2025

(Date)



**Entergy Services, LLC**  
**Mississippi Environmental Support**  
3889 Beasley Road  
Jackson, MS 39213-3603  
Telephone: (601) 321-3832  
Email: [bgriff7@entergy.com](mailto:bgriff7@entergy.com)  
Beau Griffin, Environmental Analyst

---

January 30, 2025

Mr. Greg Mallery  
Air Division  
Asbestos and Lead Group  
Office of Pollution Control  
P. O. Box 2261  
Jackson, MS 39225

RE: Entergy Mississippi, LLC – Gerald Andrus Plant  
Annual Asbestos Notifications for Routine Maintenance

Dear Mr. Mallery:

Enclosed is the annual notification for removal of regulated asbestos containing materials at the Gerald Andrus Plant. This notification is submitted to comply with 40 CFR 61.145(a) (4) (iii) which states that the removal of asbestos containing material should be predicted for the calendar year.

This notification is being submitted in the event that the specified quantities of asbestos material are removed during routine maintenance of boiler valves, packing and pipe insulation. Individual notifications will also be submitted as required.

All asbestos containing material will be adequately wet during removal and handling and will be placed in labeled plastic bags. Filled bags will not be dropped or thrown. Waste filled bags will be transported to the local permitted solid waste landfill for disposal.

If additional information is needed, please contact Tasha Hill at 501-258-8977 ([thill1@entergy.com](mailto:thill1@entergy.com)) or Beau Griffin at 601-466-4477 ([bgriff7@entergy.com](mailto:bgriff7@entergy.com)).

Respectfully submitted,

A handwritten signature in blue ink that reads "Beau Griffin". The signature is stylized and includes a large flourish at the end.

Beau Griffin  
Sr. Environmental Analyst

Enclosures